### **Bud Clark Commons**

## **Project Overview**



Bud Clark Commons; Dusk view from SW. - Photo Credit: Christian Columbres Photography

As a centerpiece of Portland's Ten Year Plan to End Homelessness, Bud Clark Commons (BCC) represents a new approach to providing dignified housing and comprehensive services to help those experiencing homelessness. Funded by a combination of low-income housing tax credits, urban renewal funding, and HUD stimulus dollars, the project sets a new standard by combining permanent supportive housing and temporary shelter with a community resource center.

Located at the gateway to downtown Portland near historic Union Station, BCC sits between the Pearl District, an upper-income mixed-use neighborhood, and Old Town/Chinatown, a district undergoing an unprecedented level of redevelopment. The LEED Platinum project achieves a perceivable balance between the rigorous programmatic requirements of a coalition led by the City of Portland, a progressive design approach, and sustainable building practices.

The project's mission is to provide a continuum of services to help transition homeless individuals toward stable, permanent living arrangements. The architecture helps achieve this goal in the expression of both form and function: a walk-in day center with public courtyard and access to services; a 90-bed temporary shelter; and a separate and secure entrance to 130 efficient, furnished studio apartments for homeless men or women seeking permanent housing with support services.

#### Location:

655 NW Hoyt Street
Portland Oregon 97209
United States
Project Owner:
Home Forward

**Submitting Architect:** 

.

Holst Architecture

**Project Completion Date:** 

June, 2011

**Project Site:** 

**Brownfield Site** 

**Project Type:** 

Mixed - Use

Office - 10,001 to 100,000sf

Public Assembly - Social/Meeting

Residential – Multi-Family 5 or more units

**Project Site Context/Setting:** 

Urban

Other Building Description:

New

**Building or Project Gross Floor Area:** 

106,000 square feet

**BOMA Floor area method used?:** 

No

**Hours of Operation:** 

24/7

Total project cost at time of completion, land excluded:

\$28,750,000.00

## **Design & Innovation**



Overview of Bud Clark Common's sustainable features and innovations. -Photo Credit: Holst Architecture

.

Sustainability at BCC meant creating a durable place of dignity for our most vulnerable citizens while treading lightly on the planet. The team creatively combined three disparate program elements with similar missions on a tight urban site, conserving land and maximizing the city's density, mixed-use, and transit-oriented goals. The designers considered the users' health and wellbeing in every design decision, and employed energy-saving technologies, materials, and construction methods to ensure that public resources were used wisely.

The key environmental issues at BCC are particularly complex given its population. We had to consider the need for outdoor space for users to congregate, wait for services, and to

experience nature amidst an urban environment. Access to daylight was balanced with the need for privacy, achieved with filtered views, borrowed light from courtyards, and relites. Clear, safe, and efficient wayfinding was essential; simple entrances and ramps to each public program component allow for universal access.

The key concepts for this project were social equity and the triple bottom line: sustainability that includes financial, social, and environmental performance measures. We wanted to create an energy-efficient building for financial sustainability, environmental stewardship, and as a distinguishing element to support the mission of this vital facility.

# Regional/Community Design



Aerial view of Bud Clark Commons showing its vital urban context. BCC sits on the western border of Old Town/Chinatown, an emerging historical neighborhood in Portland, and the eastern border of the Pearl District, an upscale mixed-use neighborhood. Its visibility from Portland's bustling train station, directly to its north, and from the Broadway Bridge, symbolizes the city's dedication to ending homelessness. - Photo Credit: **SkyShots** 



North view of Bud Clark Commons, looking downtown from Portland's central train station. - Photo Credit: Sally

#### Schoolmaster



Bud Clark Commons' public courtyard, sheltered from the traffic and street, provides a safe and dignified place for homeless individuals seeking services to wait, socialize, and experience nature within an urban environment. - Photo Credit: Bruce Forster

Homelessness is not sustainable for the individual or the city.

Nearly 2,000 people are on the streets each night in Portland, Oregon. Contributing factors of unemployment and long-term poverty range from domestic violence, untreated physical and mental illnesses, and disabilities to alcoholism and drug abuse. The costs and impacts of homelessness are significant and difficult to quantify, so we committed to achieving sustainability in a second way: social sustainability and those immeasurable qualities of the human condition, safety, independence, and health.

The project provides 130 permanent apartments for the most vulnerable homeless, many suffering from compromised mental and/or physical health. The 90-bed temporary men's shelter is offered to clean, sober men actively looking for work. The project's Day Center offers support services such as drug and alcohol counseling, showers, telephones, mail service, job training, classes, and community space, available to any male or female homeless individuals on a walk-in basis.

Parking was intentionally excluded to save space for critical program elements and to maximize the use of nearby alternative transportation choices including light rail, train, and bus services. Drawing people off the street, BCC's courtyards have become transformative places that set forth a positive environment of hope, dignity, and respect.

### **Metrics**

Estimated percent of occupants using public transit, cycling or walking: 95%

## Land Use & Site Ecology

.



Bud Clark Commons' brownfield site was previously occupied by a gas station and asphalt parking lot. - Photo Credit: Holst Architecture / Photo by SkyShots



The construction of Bud Clark Commons - and the intentional exclusion of parking lots or spaces promotes density and infill, turning zero floor area ratio (FAR) into 6:1 FAR and maximizing allowable zoning density and height goals. It also resulted in soil remediation, stormwater management for runoff from the adjacent bridge, and reinforcement for the bridge itself. - Photo Credit: Holst Architecture / Photo by **SkyShots** 

.

The building had been conceived as a full-block, two- and six-story building with wood construction, but it was revised to become a half-block, 8-story concrete structure. The smaller footprint reduced the cost of land acquisition, and the greater height is closer to the maximum allowed on its site, making it a better fit for the city's density goals.

The exclusion of parking lots or spaces promotes density and infill on what was a brownfield site, turning zero floor area ratio (FAR) into 6:1 FAR, maximizing allowable zoning density and


height goals, while creating a gateway building and icon at the entrance to downtown.

The brownfield site had previously housed a gas station and parking lot, which required intensive soil remediation tactics and the careful removal and treatment of much of the site's excavated soil. Responding to BCC's ecological context, the team minimized excavation to avoid disturbance to groundwater, due to the building's low elevation and proximity to the Willamette River. Additionally, innovative stormwater management treats runoff from the adjacent bridge with green street planters.

## **Bioclimatic Design**



Graphic shows innovative bioclimatic design strategies used on this homeless resource center. - Photo Credit: Holst Architecture



Psychrometric Chart indicating hourly conditions and potential design strategies. - Photo Credit: PAE Consulting Engineers

.

Siting of the building was a delicate balance of trying to conserve half of the block, utilizing grade change to maximize universal access to multiple floors, and addressing appropriate street frontages for both the users and the city's goals around the public realm (retail wants to be on light rail line so we oriented away from 6th avenue toward the less-trafficked Broadway).

The design team realized that the micro-residential units would be primarily heated by the residents and refrigerators inside, so there was less need for robust heating technologies. To further reduce or eliminate the need for non-renewable energy resources, the team


incorporated strategies such as solar hot water, graywater harvesting, heat recovery ventilation, green power purchasing, and electric (as opposed to natural gas) air handling units.

Courtyards were situated to maximize exposure to sunlight both now and when projected future developments are completed on the adjacent lot to the east, and on the block across the street to the south. The team placed the courtyards as far away from future shadow lines as possible. Additionally, the team selected many species of native, drought-tolerant plants for the courtyards, which are more likely to thrive in the local climate.

# **Light & Air**



Air flow/leakage found in typical affordable studio apartment. - Photo Credit: Holst Architecture / PAE Consulting Engineers



Air flow in Bud Clark
Commons' residential
apartments, featuring Heat
Recovery Units, electric
valence heaters placed high
on wall to maximize floor
space and safety for
residents, and window
watcher thermostat that turns
off heat when window is
opened. - Photo Credit: Holst
Architecture / PAE Consulting
Engineers



Generous daylighting and LED lighting used in one of Bud Clark Common's community rooms. - Photo Credit: Sally Schoolmaster

.

The building's residents and staff greatly benefit from natural light, plentiful clean air, and energy-efficient lighting. The ample daylighting and views of nature give users a connection between indoors and outdoors. Courtyards and balconies are additional sources of light, and areas on each of the eight floors also offer some access to the outdoors.

Floor-to-ceiling windows on the ground level extend the length of the west façade, the abundance of glazing allowing natural light to saturate the interior. A comfortable year-round temperature is maintained through a highly efficient sensor that shuts off the heater when the window is open. Fresh air is circulated into each apartment through a heat recovery system.

An issue unique to this project type, tuberculosis control necessitated additional air exchange rates and UV air treatment in assembly and group living spaces. Displacement ventilation strategies, which are extremely rare in homeless shelters, provide maximum air changes without sacrificing comfort for a compromised population.

#### **Metrics**

Daylighting at levels that allow lights to be off during daylight hours:

55%

Views to the Outdoors:

55%

Within 15 feet of an operable window:

35%

## **Water Cycle**



View of landscaped courtyards, featuring stormwater treatment, bioswales, and droughttolerant native landscaping. -Photo Credit: Sally Schoolmaster



View of custom rainwater collection and stormwater treatment system. - Photo Credit: Sally Schoolmaster



Another view of custom rainwater collection and stormwater treatment system. - Photo Credit: Sally Schoolmaster

BCC features eco-roofs and stormwater treatment systems that are well integrated into the two courtyards. Rainwater is collected from roofs, and then exhibited in the courtyards via stormwater planters designed in concert with public art.

A significant innovation of this project includes graywater harvesting on a large, urban

.

scale—rarely if ever incorporated at homeless facilities. The graywater recycling system captures water from showers and washing machines to flush toilets, reducing the water needs and usage of the building.

Low-flow plumbing fixtures further reduce water usage in the building, and a solar-powered hot water system provides almost all of the hot water needs for the building year-round.

A landscaped courtyard with seating, tables, and a bioswale water feature provide a transitional space between the street and the safety of the day center. Native landscaping, non-invasive species, low water use, and zero permanent irrigation results in zero stormwater runoff. The team created lush outdoor courtyards and vegetated roofs where there was previously asphalt, a welcome change for wildlife and humans alike.

#### **Metrics**

Percent reduction of regulated potable water:

53%

Is potable water used for irrigation:

No


Percent of rainwater from maximum anticipated 24 hour, 2-year storm event that can be managed onsite:

52%

## **Energy Flows & Energy Future**



Aerial view of Bud Clark Commons' onsite PV array. -Photo Credit: SkyShots



Through energy conservation

measures such as heat recovery, increased thermal performance, and solar hot water, we were able to achieve a 45% savings of energy use over comparable code baseline designs. - Photo Credit: Holst Architecture / PAE Consulting Engineers

.

BCC earned LEED Platinum certification, with public savings from the use of energy-efficient technologies estimated at \$60,000 per year. BCC features a range of highly efficient systems, including one of the largest solar hot water heating systems in the Pacific Northwest, satisfying 80% of the building's hot water needs. The building's tight and highly efficient thermal envelope significantly reduces its heating load. A heat recovery system for residential units, Energy Star appliances, and low-flow plumbing fixtures throughout the building further enhance energy and water savings.

The project's lighting design exceeds energy code requirements by 25% through the use of fluorescent and LED sources. Extensive electrical and water metering allow for the tracking of mechanical, lighting, and water system performance. The building performs 51% better in terms of energy efficiency and 53% better in water efficiency than a typical similar building.

While the building is more heavily used than originally anticipated, the energy savings compared to the typical similar building is still significant. Between the efficiency strategies and the purchased green power, the project meets the current 2030 Challenge target of 60% CO2 reduction. Most importantly, the resulting utility cost savings allow for more funds to be directed to BCC's mission and the services it provides.

#### **Metrics**

Total pEUI:

80 kBtu/sf/yr

Net pEUI:

76 kBtu/sf/yr

Percent Reduction from National Median EUI for Building Type (predicted):

51%

**Lighting Power Density:** 

0.63 watts/sf

**Upload Energy Data Attachment:** 

7. Energy Metrics\_BCC.jpg

### **Materials & Construction**



The building features two courtyards that are both constructed with durable materials such as painted concrete and weathering steel, a recycled and recyclable product. Many materials used in the building's construction are either locally sourced or sustainably harvested and produced, including local brick, local concrete, and local, FSC-certified interior siding and trim. - Photo Credit: Sally Schoolmaster



A close-up of durable, sustainable materials including local brick, local concrete, and recycled weathering steel. - Photo Credit: Sally Schoolmaster

.

Materials for this project were chosen specifically for their ability to optimize the health of residents, many of whom suffer from illnesses; durability and maintenance; and energy use, given the public nature of the project and its need for cost savings.

The building features two courtyards that are both constructed with durable materials such as painted concrete and weathering steel, a recycled and recyclable product. Many materials used in the building's construction are either locally sourced or sustainably harvested and produced, including local brick, local concrete, and local, FSC-certified interior siding and trim.

In an effort to reduce the amount of materials used on the project, its concrete structure serves as the flooring and ceiling in many areas. The use of thicker continuous exterior insulation allowed us to eliminate insulation in the stud cavity. We incorporated Passive House concepts for the residential floors with high-performing fiberglass windows and continuous insulation "perfect wall" assembly, in addition to an IRMA roof that keeps dew point and moisture out of wall and ceiling cavities.

Additionally, a building-wide recycling plan, recycling stations on each floor, green housekeeping training, and free green supplies for tenants help promote recycling and environmental stewardship for occupants.

## Long Life, Loose Fit



Homeless resource center's entrance, ramp, and lockers demonstrating adaptive reuse potential. - Photo Credit: Sally Schoolmaster



Homeless resource center's staff conference room demonstrating adaptive reuse potential. - Photo Credit: Sally Schoolmaster



Homeless resource center's hallway and meeting room demonstrating adaptive reuse potential. - Photo Credit: Sally Schoolmaster


.

Durability was a top priority for this publicly funded, sustainably minded project. The team made constant and deliberate value decisions to invest in long-lasting solutions rather than accepting immediate savings; examples include solid surface counters, solid core doors, higher performing windows, durable brick and concrete skin, and post-tensioned concrete structure (as opposed to wood framing).

The team designed BCC to be a 100-year building, but parts and pieces are meant to be accessible and replaceable over time as technologies improve or advance. Examples of these replaceable parts include the rooftop equipment, solar hot water system, and windows. Notably, the windows were specifically designed to be replaced without impacting the brick façade.

The building's concrete structure is a durable framework that allows for future uses. It was purpose-built but could potentially be repurposed for senior or student housing, or a long-term-stay hotel. The layout and program are conducive to these other potential uses: a courtyard leads to a welcoming lobby, with community and administrative spaces, a commercial kitchen, yoga and art rooms, and efficiency apartments with galley kitchens.

### **Collective Wisdom & Feedback Loops**



We chose to install a graywater system rather than a rainwater system for four reasons: 1. The State of Oregon had recently begun to allow graywater recycling in commercial buildings and our client wanted to us this project as a case study. 2. Stormwater management was already being implemented in the design to limit runoff of rainwater. 3. Significant sewer cost savings could be realized by recycling graywater to toilets. 4. Because graywater is produced all year long without a dry season like rainwater, significantly smaller tanks could be installed on the tight urban site conserving space and installation cost. -Photo Credit: Holst Architecture

.

BCC is showing measurable results in both promoting housing stability among Portland's homeless, and in its building performance. In the year following BCC's opening, the client served more than 7,000 homeless persons at the day center and kitchen, including approximately 200 veterans. More than 3,600 individuals have been connected with social services, and more than 350 permanent housing placements have been made. We are conducting ongoing monitoring of building performance via mobile electrical meters that measure performance across the building and analyze plug loads and power demand.

One important lesson learned emerged from commissioning the building's innovative graywater. The designers used the only graywater system manufacturer licensed by the state at the time. There are graywater systems that are plug-and-play for small residential applications, and there are full-blown custom-designed commercial systems, and we tried to do a hybrid of the two. However, the system was too residential for this scale of development and intensity of use, so we had to revise it to utilize more robust pumps and filters, and streamline maintenance procedures to ensure staff safety. We were truly on the bleeding edge of commercial graywater for this size and type of project, and have many lessons to share.

### **Other Information**

**Cost and Payback Analysis:** 

Funded with limited public monies, rigorous cost-benefit analysis was performed to support decision-making throughout the design process. Because the client, Home Forward, plans to own and occupy Bud Clark Commons building for years to come, the project team evaluated several energy conservation measures by life cycle cost rather than the traditional first cost.

Energy and water conservation measures, with simple paybacks over longer periods than are

typically accepted by building owners, were implemented to provide reduced building operations costs. With long-term occupancy, additional savings are anticipated to be realized as energy and water rates continue to increase.

To financially support the sustainable design elements, the project was able to shift funds committed to the building operation to fund the energy efficiency measures based on the annual energy cost savings these systems would achieve. The energy and water conservation measures studied for the project include heat recovery, efficient boilers, highly efficient envelope, solar hot water, and graywater reclamation. The estimated payback for these measures is a combined 14 years.

#### **Process and Results:**

PreDesign: Arguably no building before Bud Clark Commons has had this complex program mix of homeless services on such a tight urban site, much less with such aspirational goals for sustainability. Combining three specific and intense uses in a vertically stacked program required an intense research phase before we could design the building. The entire design team held charrettes, public workshops, and visited other cities to better understand the problem and learn how this singular solution could begin to take shape. An "all hands on deck" approach was taken with the owners, engineers, consultants, contractors, tenants, neighbors, social services advocates, and the homeless community to foster a sense of ownership of the project by the entire community.

Design: Designing for people experiencing homelessness required a deft understanding of how to create warm and inviting design solutions that also stood up to high levels of use and sometimes abuse. We had to create a healing environment that lifted people's spirits while ensuring that the building could be easily cleaned, maintained, and repaired due to the extreme level of use. We liken the project to trying to combine the welcoming environment of one's home with the durability of a penitentiary.

#### Rating System(s) Results:

**Rating System:** 

LEED for New Construction v2.2

**Rating Date:** 


2011

Score or Rating

Result:

Platinum 54/69

# **Additional Images**



Context plan showing Bud Clark Commons' urban infill site and central Portland location.. - Photo Credit: Holst Architecture



Site plan showing Bud Clark Commons' central urban location and proximity to important Portland institutions. - Photo Credit: Holst Architecture



Floor plan for floors 1-2. -Photo Credit: Holst Architecture



Floor plan for floors 3-4. -Photo Credit: Holst Architecture



Floor plan for floors 5-8. -Photo Credit: Holst Architecture



Bud Clark Commons building section. - Photo Credit: Holst Architecture



Dusk view of Bud Clark Commons from southwest. -Photo Credit: Christian Columbres



View of Bud Clark Commons from the northeast, including custom entrance gate that leads to public courtyard for the homeless seeking services and shelter. - Photo Credit: Sally Schoolmaster

# **Project Team and Contact Information**

### **Primary Submission Contact:**

### **Xylia Buros**

xburos@holstarc.com Holst Architecture 110 SE 8th Ave Portland Oregon 97214 United States

### **Project Architect (if different from submission contact):**

### Dave Otte, AIA

dotte@holstarc.com Holst Architecture 110 SE 8th Ave Portland Oregon 97214 United States

### **Project Team:**

| Role on Team       | First<br>Name | Last Name   | Company            | Location        |
|--------------------|---------------|-------------|--------------------|-----------------|
| Owner              | Steve         | Rudman      | Home Forward       | Portland,<br>OR |
| Owner              | Mike          | Andrews     | Home Forward       | Portland,<br>OR |
| Owner              | Julie         | Livingston  | Home Forward       | Portland,<br>OR |
| Architect; Partner | Jeffrey       | Stuhr       | Holst Architecture | Portland,<br>OR |
| Architect; Partner | John          | Holmes, AIA | Holst Architecture | Portland,<br>OR |

| DesignerKimWilsonHolst ArchitecturePortland, ORRDesignerCoryHawbeckerHolst ArchitecturePortland, ORRDesignerKatherineDeckerHolst ArchitecturePortland, ORGeneral Contractor; PresidentBobWalshWalsh Construction Co.Portland, ORGeneral Contractor; VPMikeSteffenWalsh Construction Co.Portland, ORStructural EngineerRandallToma, PEABHT Structural EngineersPortland, ORCivil EngineerJoshLighthipe PE, LEED AP BD&C EngineersPortland, ORMEP Engineer; PresidentPaulSchwer, PE, LEED AP BD&C (DiNola is now Executive)<br>Director at New Buildings Institute)Portland, ORLEED Documentation & CommissioningRalphDiNolaMayer/ReedPortland, OREundscape ArchitectureLindaCzopekMayer/ReedPortland, ORLandscape ArchitectureMichaelReedMayer/ReedPortland, ORCost EstimatingStanPszczolkowskiArchitectural Cost ConsultantsPortland, ORFinancingStanPszczolkowskiArchitectural Cost ConsultantsPortland, ORSheller and Day Center TenantDoreenBinderTransition ProjectsPortland, OR   | Architect; Project<br>Manager | Dave      | Otte, AIA     | Holst Architecture   | Portland,<br>OR |
|--|-------------------------------|-----------|---------------|--|-----------------|
| Designer Cory Hawbecker Holst Architecture OR  Designer Katherine Decker Holst Architecture OR  General Contractor; President General Contractor; VP Mike Steffen Walsh Construction Co. Portland, OR  Structural Engineer Randall Toma, PE ABHT Structural Engineers Portland, OR  Civil Engineer Josh Lighthipe PE, LEED AP BD&C Engineers Portland, OR  MEP Engineer; Paul Schwer, PE, LEED AP PAE Consulting Engineers Portland, OR  LEED Documentation & Ralph DiNola Green Building Services (DiNola is now Executive Director at New Buildings Institute)  Furniture Procurement Linda Czopek (Conw Czopek Design Group)  Landscape Architecture Carol Mayer-Reed Mayer/Reed Portland, OR  Cost Estimating Stan Pszczolkowski Architectural Cost Consultants Consultants  Financing Shelter and Day Dorsen Binder Transition Projects Portland, OR  | Designer                      | Kim       | Wilson        | Holst Architecture   | •               |
| General Contractor; President General Contractor; VP Mike Steffen Walsh Construction Co. Portland, OR Structural Engineer Randall Toma, PE ABHT Structural Engineers Civil Engineer Josh Lighthipe PE, LEED AP BD&C EED AP BD&C Commissioning  Ralph DiNola Documentation & Commissioning  Furniture Procurement Linda Czopek Architecture Carol Mayer-Reed Michael Architecture Cost Estimating Stan Portland, OR Walsh Construction Co. Portland, OR Civil Engineer Polivourement Civil Engineer Paul Civil Engineer Paul Civil Engineer Portland, OR Portland, OR Creen Building Services (DiNola is now Executive Director at New Buildings Institute) Czopek & Erdenberger (now Czopek Design Group) Portland, OR Cord Cord Architecture Architecture Carol Mayer-Reed Mayer/Reed Mayer/Reed Portland, OR City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo Portland, OR Port | Designer                      | Cory      | Hawbecker     | Holst Architecture   | •               |
| Contractor; President  General Contractor; VP  Mike Steffen Walsh Construction Co. OR  Structural Engineer Randall Toma, PE ABHT Structural Engineers Portland, OR  Civil Engineer Josh Lighthipe PE, LEED AP BD&C Engineers Portland, OR  MEP Engineer; Paul Schwer, PE, LEED AP BD&C Green Building Services (DiNola is now Executive Director at New Buildings Institute)  Furniture Procurement Linda Czopek Group)  Landscape Architecture Carol Mayer-Reed Mayer/Reed Portland, OR  Cost Estimating Stan Pszczolkowski Architectural Cost Consultants  Financing  Walsh Construction Co. Portland, OR  Walsh Construction Co. Portland, OR  Walsh Construction Co. Portland, OR  Portland, OR  Portland, OR  Walsh Construction Co. Portland, OR  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Portland, OR  Portland, OR | Designer                      | Katherine | Decker        | Holst Architecture   | •               |
| Contractor; VP Mike Steffen Walsh Construction Co. OR  Structural Engineer Randall Toma, PE ABHT Structural Engineers Portland, OR  Civil Engineer Josh Lighthipe PE, LEED AP BD&C Engineers Portland, OR  MEP Engineer; Paul Schwer, PE, LEED AP BD&C Green Building Services (DiNola is now Executive Director at New Buildings Institute)  Documentation & Commissioning Portland, OR  Furniture Procurement Linda Czopek Czopek & Erdenberger (now Czopek Design Group)  Landscape Architecture Carol Mayer-Reed Mayer/Reed Portland, OR  Landscape Architecture Michael Reed Mayer/Reed Portland, OR  Cost Estimating Stan Pszczolkowski Architectural Cost Consultants  Financing Stan Portland, OR  Shelter and Day Docean Binder Transition Projects Portland, OR  Fortland, OR  Portland, OR  | Contractor;                   | Bob       | Walsh         | Walsh Construction Co.   | •               |
| Civil Engineer Josh Lighthipe PE, LEED AP BD&C Engineers Portland, OR  MEP Engineer; Paul Schwer, PE, LEED AP Green Building Services (DiNola is now Executive Director at New Buildings Institute)  Furniture Procurement Linda Czopek Czopek & Erdenberger (now Czopek Design Group)  Landscape Architecture Architecture Michael Reed Mayer/Reed Portland, OR  Cost Estimating Stan Pszczolkowski City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day Dorsen Binder Transition Projects Portland, Portland, OR  KRPF Consulting Engineers OR  KRPF Consulting Engineers Portland, OR  Portland, OR  Portland, OR  Wayer/Reed Mayer/ced Portland, OR  Architectural Cost Consultants OR  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day Dorsen Binder Transition Projects Portland,   |                               | Mike      | Steffen       | Walsh Construction Co.   |                 |
| MEP Engineer; Paul Schwer, PE, LEED AP BD&C Green Building Services (DiNola is now Executive Director at New Buildings Institute)  Furniture Procurement  Linda Czopek  Carol Mayer-Reed Mayer/Reed  Architecture  Cost Estimating  Financing  Lied AP BD&C Engineers  OR  Portland, OR  Portland, OR  Cropek & Erdenberger (now Czopek Design Group)  Mayer-Reed Mayer/Reed  Architecture Cost Estimating  Stan  Pszczolkowski  Financing  Lied AP BD&C Engineers  OR  Portland, OR  Portland, OR  Portland, OR  Portland, OR  Architectural Cost Consultants  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Portland, OR  | Structural Engineer           | Randall   | Toma, PE      | ABHT Structural Engineers  |                 |
| President  LEED AP  Corean Building Services (DiNola is now Executive Director at New Buildings Institute)  Furniture Procurement  Linda  Czopek  Carol  Architecture  Architecture  Cost Estimating  Stan  Cost Estimating  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Creen  Binder  Cropek  Green Building Services (DiNola is now Executive Portland, OR  Portland, OR  Portland, OR  Architector at New Buildings Institute)  Portland, OR  Portland, OR  Portland, OR  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Portland, OR  | Civil Engineer                | Josh      | •             | 3  | •               |
| Documentation & Commissioning  Ralph DiNola  DiNola  (DiNola is now Executive Director at New Buildings Institute)  Furniture Procurement  Linda Czopek Czopek & Erdenberger (now Czopek Design Group)  Landscape Architecture  Landscape Architecture  Michael Architecture  Michael Architecture  Cost Estimating  Stan  Pszczolkowski  Architectural Cost Consultants Consultants  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Dorsen  Rinder  Ralph  DiNola  (DiNola is now Executive Director at New Buildings Institute)  Portland, OR  | _                             | Paul      |               | PAE Consulting Engineers   | •               |
| Procurement  Linda  Czopek  (now Czopek Design Group)  Portland, OR  Architecture  Architectural Cost Consultants  Consultants  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Portland, OR  | Documentation &               | Ralph     | DiNola        | (DiNola is now Executive Director at New Buildings   | •               |
| Architecture  Landscape Architecture  Michael Reed  Mayer/Reed  Mayer/Reed  Mayer/Reed  Portland, OR  Cost Estimating  Stan  Pszczolkowski  Architectural Cost Consultants  Consultants  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Doreen  Rinder  Reed  Mayer/Reed  OR  Portland, OR   |                               | Linda     | Czopek        | (now Czopek Design   | •               |
| Architecture  Cost Estimating  Stan  Pszczolkowski  Consultants  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Doreen  Reed  Mayer/Reed  OR  Architectural Cost Consultants  Portland, OR   | •                             | Carol     | Mayer-Reed    | Mayer/Reed   | •               |
| Cost Estimating  Stan  Pszczolkowski  Consultants  OR  City of Portland, State of Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Dorsen  Binder  Transition Projects  Portland, OR  Portland, OR  Portland, OR  Portland, OR  | -                             | Michael   | Reed          | Mayer/Reed   | •               |
| Financing  Oregon, Multnomah County, US Department of Housing & Urban Development, and Wells Fargo  Shelter and Day  Dorsen Binder  Transition Projects  Portland, OR  Portland,   | Cost Estimating               | Stan      | Pszczolkowski |  | •               |
| Y LIGITAGE RINGER LIGITION PROJECTS  | Financing                     |           |               | Oregon, Multnomah<br>County, US Department of<br>Housing & Urban<br>Development, and Wells | •               |
|  | •                             | Doreen    | Binder        | Transition Projects  |                 |

Source URL: http://www.aiatopten.org/node/402